


# **Installation manual**

## Daikin Altherma – Low temperature split



KONFORMITÄTSERKLÄRUNG DECLARATION-DE-CONFORMITE CONFORMITEITSVERKLARING

CE - DECLARACION-DE-CONFORMIDAD CE - DICHIARAZIONE-DI-CONFORMITA CE - ΔΗΛΩΣΗ ΣΥΜΜΟΡΦΩΣΗΣ

CE-DECLARAÇÃO-DE-CONFORMIDADE CE-3ARBIEHÚR-O-COOTBETCTBUN CE-OVERENSSTEMMELSESERKLÆRNG CE-FÖRSÄKRAN-OM-ÖVERENSTÄMMELSE

ម៉ូម៉ូម៉ូ

ERKLÆRING OM-SAMSVAR ILMOITUS-YHDENMUKAISUUDESTA PROHLÁŠENÍ-O-SHODĚ

ម៉ូម៉ូម៉ូម៉ូ

- IZJAVA-O-USKLAĐENOSTI -- MEGFELELŐSÉGI-NYILATKOZAT -- DEKLARACJA-ZGODNOŚCI -- DECLARAŢIE-DE-CONFORMITATE

CE - IZJAVA O SKLADNOSTI CE - VASTAVUSDEKLARATSIOON CE - JEKTIAPALJAR-3A-C'BOTBETCTBME

CE - ATTÍKTIES-DEKLARACIJA CE - ATBILSTĪBAS-DEKLARĀCIJA CE - VYHLÁSENIE-ZHODY CE - UYGUNLUK-BEYANI

# Daikin Europe N.V.

EHVH04S23DAV\*, EHVH08S23DAV\*, ∵= ... G

заявляет, исилочительно под свою ответственность, что оборудование, к которому относится настоящее заявление: eiklæser under eixensisarlig, at udstyret, som er omfattet af denne erklæering: deklareari egenskap ar huvidarsvång, attritrishingen som berörs av derina deklaration innebär att. erktærer et fullstendig ansvar for at det utskyr som benøres av denne deklarasjon innebærer at: linnottaa yksinomaan onnalla tvastuulaan, että färnän linnottuksen tarkottamat latteet. 

# ord (a) declares under its sole responsibility that the equipment to which this declaration reades. 10.5 or effort and seeme alkinge behankrung but die Musikurguing für die deset Addrung bestimmt ist: 10.6 declara sols a seuller responsibilité que l'equipment visé par la présente déclaration. 10.6 declara sols a seuller responsibilité que l'equipment visé par la présente déclaration. 10.6 declara sols sui der responsibilité que l'equipment visé par la présente de déclaration. 10.7 delia suito imprire responsabilité que le depute du finat questa dichiarazione. 10.7 delia suito imprire responsabilité que le depute du finat questa dichiarazione. 10.9 declara sols suita exclusiva responsabilité due que se equipment se que esta declarazione.

pohlašuje ve své prie odpovědnosti. že zařízení, k němuž se toto pohlášení vzahluje: zjavljuje pod iskljuživo vlastitom odgovomošču da oprema na koju se ova izjava odnost teljes felefossége tudatázan kljelenti, hogy a berendezések, melyekre e nyllatkozat vonatkozík:

17 © deklanije na wkang i wijezna odpowiedziańość, że urządzenia, których la deklanaja dotyczy.
18 © decala pe proprie detychurche ce dechipamelbe la care de refe a cesaśł decaraje:
18 © z vso odpownosticj zgłąd, ad je oprena ragzar, na kalero se zgłąd narata;
18 © kranipam czych orgenia ragzar, na kalero se zgłąd narata;
18 © prenapynej na czych orgenia ragzar, na kalero se zgłąd naratą;
18 © wiskas savio adskomyte selbay, kad pingą, kural inkomia si okłanają.
18 © wiskas savio adskomyte selbay, kad pingą, kural inkomia śli okłanają.
18 © wiskas savio adskomyte selbay sak sak sak sie kadza sa z kożenia zdopowerna; że zaradanie sa tok okłanając.
18 © wyklasuje na vlastu zdopowerna; że zaradanie na tok okłanając.
18 © wyklasuje na vlastu zdopowerna; że zaradanie na tok okłanając.
18 © wiłasuje na vlastu zdopowerna; że zaradanie z tok okłanając.
18 © wiłasuje na vlastu zdopowerna; że zaradanie z tok okłanając.

der/den fotgenden Norm(en) oder einem anderen Normdokument oder -dokumenten entspricht/entsprechen, unter der Voraussetzung, daß sie gemäß are in conformity with the following standard(s) or other normative document(s), provided that these are used in accordance with our instructions: unseren Anweisungen eingesetzt werden:

sont conformes à lafaux noime(s) ou autre(s) document(s) normatif(s), pour autant qu'ils soient utilisés conformément à nos instructions: conform de volgende norm(en) of één of meer andere bindende documenten zijn, op voowaarde dat ze worden gebuikt overeenkomstig onze

están en conformidad con la(s) siguiente(s) norma(s) u otro(s) documento(s) normativo(s), siempre que sean utilizados de acuerdo con nuestras 92

sono conformi ali() seguente(i) standard(s) o altro(i) documento(i) a carattere normativo, a patib che vengano usati in conformità alle nostre istruzioni: είναι σύμφωνα με το(σ) ακόλουθο(ο) πρότυπο(σ) ή άλλο έγγραφο(σ) κατονισμών, υπό την προύπθέσση ότι χρισιμοπορώτα αύμφωνα με τις οδηγίες μας:

08 estão em conformidade com a(s) seguinte(s) norma(s) ou outro(s) documento(s) normativo(s), desde que estes sejam utilizados de acordo com as nossas instruções:

соответствуют стедующим стандатам или другим нодалятивым доументам, тру устовим их истолькавамя сотражно нетрумциям, очегловет figendes standardled ne entringsjewerbe dumentlen), foruds at dissea amendes i henhold it voe instrukser. essektive utusting at utgot for veerstaamees med cost fige fidende standard(e) elle andra normgivande dux ment under trousslaming at 3 9 5

aménding sker l'overensstammelse med via a ristuktoner.

12. respoktive ustry et noverenssemmelse med fagande standarder eller andre normgivende dokumentide udber fourbesening av at disse brukes i henhoti til vale instruker.

13. vaskaade standarder eller el

spehiają wymogi nasiąpujących norm i innych dokumentów normalizacyjnych, pod warunkiem że używane są zgodnie z naszymi nistrukcjami: suntin conformijale cu umatorui (umatoarele) standardie) sau attie) documentie) normatiwie), cu condiția ca acestea să fie utilizate în conformitate cu Instruction transaction frankard in drugini normativi, pod pogojem, da se uporabljajo v skladu z našimi ravodili:

20. on vrastavnes grignitis (Paradizardile) ga vile sele normativese dormanitese a se podorio valura ormanitese dormanitese dormani megfelelnek az alábbi szabvány(ok)nak vagy egyéb irányadó dokumentum(ok)nak, ha azokat előírás szerint használják: instrucțiunile noastre: 9 1 9

návodom: ūrūnūn, talimatlanmiza göre kullanılması koşuluyla aşağıdaki standartlar ve norm belirten belgelerle uyumludur;

18 Directiver, med severe andringer.
19 Directiver, med severe andringer.
19 Directiver consistent andringer.
19 Directiver severe andringer.
20 Directiver severe severe

6 = 5 6 4 6 6 6

01 Directives, as amended.
02 Directives, as amended.
03 Directives, letter and Anderung.
03 Directives, letter an modifiers.
04 Richtlighen, zoals geamendeerd.
05 Directives, seguin for emmedato.
07 Orghwis virus, stour viporimmelled.
09 Directives, conforme alteração em.
09 Directives, conforme alteração em.

Low Voltage 2014/35/EU

# EN60335-2-40

10 under iggitagelse af bestemmelserne i: 11 enligt villoder i. 12 girt ihenhold ibestemmelserne i: 13 noudstlaen määräyksiä: 14 za doorben kisaloven předpisu: 15 prema odreboma: 16 követa al.; 17 zgodné z postanowiemmi Dyrektyw: 18 in uma pravedeníor. 06 Nota\* as set out in <A> and judged positively by <B> following the provisions of:
gemäß den Vorschriften der:
conformément aux stipulations des:
tovereenkomstig de bepalingen van: με τήρηση των διατάξεων των: de acordo com o previsto em: в cooтветствии с положениями: siguiendo las disposiciones de: secondo le prescrizioni per: 01 Note\*

19 ob upošlevanju določb:
20 vastavati nobele:
21 cnepsalivu vrajevire + a:
22 lakanis nuostalu, paleikiamų;
22 lakanis nuostalu, paleikiamų;
23 lakalis nuostalu, paleikiamų;
24 odžiavajući ustanoventa:
25 burun ksyllarina uygun oleak;

Electromagnetic Compatibility 2014/30/EU 11 Information\* delineato nel <A> e giudicato positivamente da <B>

решением «В» осласно Свидетельству <C».</p>
som anført i <A» og positivt vurderet af <B» i henhold til 15 Napomena\*</p> как указано в <A> и в соответствии с положительным 14 Poznámka\* 12 Merk\* 13 Huom\* secondo il Certificatio <2>.

Orimo, kelopičino oro <4> kort pokrati Brind and <4> Certifikat <C>

zoals vermeld in <A> en positief beoordeeld door <B> 09 Примечание\*

conformément au Certificat <C>. overeenkomstig Certificaat <C>

03 Remarque\* 02 Hinweis\*

04 Bemerk\*

05 Nota\*

10 Bemærk\*

como se establece en <A> y es valorado positivamente por <B> de acuerdo con el Certificado <C>.

07 Σημείωση\*

according to the Certificatie <C>.

When I AP Angelight and vor 4B positiv
beurteit gemät Zerffittet <C>.

Butteit gemät Zerffittet <C>.

Bit que défini dans <4P et évalué positivement par <B> 08 Nota\*

a(z) <A> alapján, a(z) <B> igazolta a megfelelést, a(z) 21 Забележка\* asa cum este stabilit în <A> și apreciat pozitiv de <B> 23 Piezimes\* în conformitate cu Certificatul <C> nagu on näidatud dokumendis <**A>** ja heaks kiidetud <**B>** järgi vastavalt sertifikaadile <**C>**. kot je določeno v < A> in odobreno s strani < B> C> tanúsítvány szennt zgodnie z dokumentacją <A>, pozytywną opinią <B> i Świadectwem <C> v skladu s certifikatom < 16 Megjegyzés\* 19 Opomba\* ijsk bylo uvedeno v <A> a pozitivně zijštěno

Pb. v souladu s sevetědenim <C>.

Rako je boženo u <A> i pozitivno ocjenjeno od strane 20 Markus\*

Rako je boženo u <A> i pozitivno ocjenjeno od strane 20 Markus\*

Pb. prema Gerffilkatu <C>. 17 Uwaga\* 18 Notă\*

som det fremkommer i <A> og gjennom positiv bedømmelse av <B> ifølge Sertifikat <C> jotka on esitetty asiakiŋassa <A> ja jotka <B> on hyväksynyt Sertifikaatin <C> mukaisesti.

enligt <A> och godkänts av <B> enligt Certifikatet <C>.

както е изложено в <A> и оценено положително от <B> съгласно **Сертификата <С>** kaip nustatyta **<A>** ir kaip teigiamai nuspręsta **<B>** pagal

22 Pastaba\*

ako bolo uvedené v <A> a pozitívne zistené <B> v súlade kā norādīts <A> un atbilstoši <B> pozitīvajam vērtējumam <A>'da belirtildiği gibi ve <C> Sertifikasına göre <B> tarafından olumlu olarak değerlendirildiği gibi. saskaņā ar sertifikātu < s osvedčením <C>.

25 Not\*

<A> DAIKIN.TCF.034/09-2017 <C> 2192529.0551-EMC <B> DEKRA (NB0344)

DAIKIN EUROPE N.V.

Zandvoordestraat 300, B-8400 Oostende, Belgium

DAIKIN

Director

Shigeki Morita

Ostend, 2nd of October 2017

3P507286-5

#### **Table of contents**

Abo	out the	documentation
1.1	About t	his document
Abo	out the	box
2.1	Indoor	unit
	2.1.1	To remove the accessories from the indoor unit
	2.1.2	To handle the indoor unit
Pre	paratio	on
3.1	Prepari	ng the installation site
	3.1.1	Installation site requirements of the indoor unit
3.2		ng water piping
	3.2.1	To check the water volume and flow rate
3.3	3.3.1	ng electrical wiring  Overview of electrical connections for external and
	3.3.1	internal actuators
Inst	allatio	in .
4.1		g the units
	4.1.1	To open the indoor unit
	4.1.2	To open the switch box cover of the indoor unit
	4.1.3	To lower the switch box on the indoor unit
4.2		ng the indoor unit
	4.2.1	To install the indoor unit
4.0	4.2.2	To connect the drain hose to the drain
4.3	4.3.1	ting the refrigerant piping  To connect the refrigerant piping to the indoor unit
4.4		ting the water piping
	4.4.1	To connect the water piping
	4.4.2	To connect the recirculation piping
	4.4.3	To fill the water circuit
	4.4.4	To fill the domestic hot water tank
	4.4.5	To insulate the water piping
4.5		cting the electrical wiring
	4.5.1	To connect the electrical wiring on the indoor unit
	4.5.2 4.5.3	To connect the main power supply  To connect the shut-off valve
	4.5.4	To connect the electrical meters
	4.5.5	To connect the domestic hot water pump
	4.5.6	To connect the alarm output
	4.5.7	To connect the space heating ON/OFF output
	4.5.8	To connect the changeover to external heat source
	4.5.9	To connect the power consumption digital inputs
	4.5.10	To connect the safety thermostat (normal closed
	4.5.11	To connect the anti-legionella heater power supply
4.6		ng the indoor unit installation
	4.6.1	To close the indoor unit
Cor	ifigura	ntion
5.1	_	ew: Configuration
	5.1.1	To access the most used commands
5.2	•	ıration wizard
	5.2.1	Configuration wizard: Language
	5.2.2	Configuration wizard: Time and date
	5.2.3	Configuration wizard: System
	5.2.4	Configuration wizard: Main zone
	5.2.5	Configuration wizard: Additional zone
	5.2.6 5.2.7	Configuration wizard: Additional zone  Detailed screen with weather-dependent curve
	5.2.7	Configuration wizard: Tank
5.3		s menu
-	5.3.1	Main zone
	5.3.2	Additional zone
	5.3.2 5.3.3	Additional zone

6	Commissioning				
	6.1 Checklist before commissioning				
	6.2	Checklist during commissioning	20		
		6.2.1 To check the minimum flow rate	20		
		6.2.2 To perform an air purge	20		
		6.2.3 To perform an operation test run	21		
		6.2.4 To perform an actuator test run	21		
		6.2.5 To perform an underfloor heating screed dryout	21		
7	Har	nd-over to the user	22		
8	Tec	chnical data	23		
	8.1	Piping diagram: Indoor unit	23		
	8.2	Wiring diagram: Indoor unit	24		
	8.3	Table 1 – Maximum refrigerant charge allowed in a room:			
		indoor unit	27		
	8.4	Table 2 – Minimum floor area: indoor unit	27		
	8.5	Table 3 – Minimum venting opening area for natural			
		ventilation: indoor unit	27		

#### 1 About the documentation

#### 1.1 About this document

#### Target audience

Authorised installers

#### **Documentation set**

This document is part of a documentation set. The complete set consists of:

- General safety precautions:
  - Safety instructions that you must read before installing
  - Format: Paper (in the box of the indoor unit)
- Indoor unit installation manual:
  - · Installation instructions
  - Format: Paper (in the box of the indoor unit)
- Outdoor unit installation manual:
  - · Installation instructions
  - Format: Paper (in the box of the outdoor unit)
- Installer reference guide:
  - Preparation of the installation, good practices, reference data,...
  - Format: Digital files on http://www.daikineurope.com/supportand-manuals/product-information/
- Addendum book for optional equipment:
  - · Additional info about how to install optional equipment
  - Format: Paper (in the box of the indoor unit) + Digital files on http://www.daikineurope.com/support-and-manuals/productinformation/

Latest revisions of the supplied documentation may be available on the regional Daikin website or via your dealer.

The original documentation is written in English. All other languages are translations.


#### Technical engineering data

- A subset of the latest technical data is available on the regional Daikin website (publicly accessible).
- The full set of latest technical data is available on the Daikin extranet (authentication required).

#### 2 About the box

#### 2.1 Indoor unit


#### 2.1.1 To remove the accessories from the indoor unit



- Shut-off valves for water circuit
- b Overpressure bypass valve
- General safety precautions
- Addendum book for optional equipment
- Indoor unit installation manual
- Operation manual
- Sealing rings for shut-off valves (space heating water g circuit)
- Sealing rings for field-supplied shut-off valves (domestic hot water circuit)
- Sealing tape for low voltage wiring intake

#### 2.1.2 To handle the indoor unit

Use the handles at the back and at the bottom to carry the unit.



- Handles at the back of the unit
- Handles at the bottom of the unit. Carefully tilt the unit to the back so that the handles become visible.

#### 3 **Preparation**

#### 3.1 Preparing the installation site



#### **WARNING**

The appliance shall be stored in a room without continuously operating ignition sources (example: open flames, an operating gas appliance or an operating electric heater).





#### WARNING

DO NOT reuse refrigerant piping that has been used with any other refrigerant. Replace the refrigerant pipes or clean thoroughly

#### 3.1.1 Installation site requirements of the indoor unit

- The indoor unit is designed for indoor installation only and for the following ambient temperatures:
  - Space heating operation: 5~30°C
  - Domestic hot water production: 5~35°C
- Mind the following spacing installation guidelines:





#### INFORMATION

If you have limited installation space, do the following before installing the unit in its final position: "4.2.2 To connect the drain hose to the drain" on page 8. It requires to remove one or both side panels.

#### Special requirements for R32



#### **WARNING**

- Do NOT pierce or burn.
- Do NOT use means to accelerate the defrosting process or to clean the equipment, other than those recommended by the manufacturer.
- Be aware that R32 refrigerant does NOT contain an odour.



#### **WARNING**

The appliance shall be stored so as to prevent mechanical damage and in a well-ventilated room without continuously operating ignition sources (example: open flames, an operating gas appliance or an operating electric heater) and have a room size as specified below.



#### NOTICE

- Do NOT re-use joints which have been used already.
- Joints made in installation between parts of refrigerant system shall be accessible for maintenance purposes.



#### **WARNING**

Make sure installation, servicing, maintenance and repair comply with instructions from Daikin and with applicable legislation (for example national gas regulation) and are executed only by authorised persons.



DAIKIN

#### NOTICE

- Pipework shall be protected from physical damage.
- Installation of pipework shall be kept to a minimum.

If the total refrigerant charge in the system is ≥1.84 kg (i.e. if the piping length is ≥27 m), you need to comply with the minimum floor area requirements as described in the following flow chart. The flow chart uses the following tables: "8.3 Table 1 – Maximum refrigerant charge allowed in a room: indoor unit" on page 27, "8.4 Table 2 – Minimum floor area: indoor unit" on page 27 and "8.5 Table 3 – Minimum venting opening area for natural ventilation: indoor unit" on page 27.




#### **INFORMATION**

Systems with a total refrigerant charge  $(m_c)$  <1.84 kg (i.e. if the piping length is <27 m) are NOT subjected to any requirements to the installation room.



#### **INFORMATION**

**Multiple indoor units.** If two or more indoor units are installed in a room, you must consider the maximum refrigerant charge that can be released in the room when a SINGLE leak occurs. **Example:** If two indoor units are installed in the room, each with its own outdoor unit, then you have to consider the refrigerant charge of the largest indoor-outdoor combination.



Unit can be installed at room A if:

- 2 ventilation openings (permanently open) are provided between room A and B, 1 at the top and 1 at the bottom.
- Bottom opening: The bottom opening must meet the minimum area requirements (VA<sub>min</sub>). It must be as close as possible to the floor. If the ventilation opening starts from the floor, the height must be ≥20 mm. The bottom of the opening must be situated ≤100 mm from the floor. At least 50% of the required opening area must be situated <200 mm from the floor. The entire area of the opening must be situated <300 mm from the floor.</li>
- Top opening: The area of the top opening must be larger than or equal to the bottom opening. The bottom of the top opening must be situated at least 1.5 m above the top of the bottom opening.
- Ventilation openings to the outside are NOT considered suitable ventilation openings (the user can block them when it is cold).

#### 3.2 Preparing water piping



#### NOTICE

In case of plastic pipes, make sure they are fully oxygen diffusion tight according to DIN 4726. The diffusion of oxygen into the piping can lead to excessive corrosion.

 Valve towards expansion vessel. The valve towards the expansion vessel (if equipped) MUST be open.

#### 3.2.1 To check the water volume and flow rate

#### Minimum water volume

Check that the total water volume in the installation is minimum 20 litres without backup heater and minimum 10 litres with optional backup heater, the internal water volume of the indoor unit NOT included.



#### **NOTICE**

When circulation in each space heating/cooling loop is controlled by remotely controlled valves, it is important that the minimum water volume is guaranteed, even if all of the valves are closed.

#### Minimum flow rate

Check that the minimum flow rate in the installation is guaranteed in all conditions. This minimum flow rate is required during defrost/backup heater operation (if applicable). For this purpose, use the overpressure bypass valve delivered with the unit, and respect the minimum water volume.



#### **NOTICE**

When circulation in each or certain space heating loops is controlled by remotely controlled valves, it is important that the minimum flow rate is guaranteed, even if all valves are closed. In case the minimum flow rate cannot be reached, a flow error 7H will be generated (no heating or operation).

See the installer reference guide for more information.

#### Minimum required flow rate

12 l/min

See the recommended procedure as described in "6.2 Checklist during commissioning" on page 20.

#### 3.3 Preparing electrical wiring

# 3.3.1 Overview of electrical connections for external and internal actuators

Item	Description	Wires	Maximum running current			
Outdoor unit and indoor unit power supply						
1	Power supply for outdoor unit	2+GND	(a)			
2	Power supply and interconnection cable to indoor unit	3	(f)			
3	Power supply for anti- legionella heater	2+GND	(c)			
4	Preferential kWh rate power supply (voltage free contact)	2	(d)			
5	Normal kWh rate power supply	2	6.3 A			
Optional equipment						

Item	Description	Wires	Maximum running current	
6	User interface used as room thermostat	2	(e)	
7	Room thermostat	3 or 4	100 mA <sup>(b)</sup>	
8	Outdoor ambient temperature sensor	2	(b)	
9	Indoor ambient temperature sensor	2	(b)	
10	Heat pump convector	2	100 mA <sup>(b)</sup>	
Field sup	plied components			
11	Shut-off valve	2	100 mA <sup>(b)</sup>	
12	Electricity meter	2 (per meter)	(b)	
13	Domestic hot water pump	2	(b)	
14	Alarm output	2	(b)	
15	Changeover to external heat source control	2	(b)	
16	Space cool/heat operation control	2	(b)	
17	Power consumption digital inputs	2 (per input signal)	(b)	
18	Safety thermostat	2	(d)	

- (a) Refer to name plate on outdoor unit.
- (b) Minimum cable section 0.75 mm<sup>2</sup>.
- (c) Cable section 2.5 mm<sup>2</sup>
- (d) Cable section 0.75 mm² till 1.25 mm²; maximum length: 50 m. Voltage-free contact shall ensure the minimum applicable load of 15 V DC, 10 mA.
- (e) Cable section 0.75 mm² till 1.25 mm²; maximum length: 500 m.
- (f) Cable section 1.5 mm<sup>2</sup>.



#### NOTICE


More technical specifications of the different connections are indicated on the inside of the indoor unit.

#### 4 Installation

#### 4.1 Opening the units

#### 4.1.1 To open the indoor unit

1 Remove the top panel.




2 Remove the user interface panel. Open the hinges at the top and slide the top panel upwards.




#### NOTICE


If you remove the user interface panel, also disconnect the cables from the back of the panel to prevent damage.




- **3** If necessary, remove the front plate. This is, for example, necessary in the following cases:
  - "4.1.3 To lower the switch box on the indoor unit" on page 7
  - "4.2.2 To connect the drain hose to the drain" on page 8
  - When you need access to the high voltage switch box



## 4.1.2 To open the switch box cover of the indoor unit






#### 4.1.3 To lower the switch box on the indoor unit


During the installation, you will need access to the inside of the indoor unit. To have easier front access, put the switch box lower on the unit as follows:

Prerequisite: The user interface panel and front panel have been removed

- 1 Remove the top panel that keeps the switch box into place at the top of the unit.
- 2 Tilt the switch box to the front and lift it out of its hinges.




3 Place the switch box lower on the unit. Use the 2 hinges located lower on the unit.



#### 4.2 Mounting the indoor unit

#### 4.2.1 To install the indoor unit


- 1 Lift the indoor unit from the pallet and place it on the floor. Also see "2.1.2 To handle the indoor unit" on page 4.
- 2 Connect the drain hose to the drain. See "4.2.2 To connect the drain hose to the drain" on page 8.
- 3 Slide the indoor unit into position.
- 4 Adjust the height of the leveling feet to compensate for floor irregularities. The maximum allowed deviation is 1°.





#### NOTICE

Do NOT tilt the unit forwards:



#### 4.2.2 To connect the drain hose to the drain


Water coming from the pressure relief valve is collected in the drain pan. The drain pan is connected to a drain hose inside the unit. You must connect the drain hose to an appropriate drain according to the applicable legislation. You can route the drain hose through the left or right side panel.

**Prerequisite:** The user interface panel and front panel have been removed.


- 1 Remove one of the side panels.
- **2** Cut out the rubber grommet.
- 3 Pull the drain hose through the hole.
- 4 Reattach the side panel. Ensure the water can flow through the drain tube.

It is recommended to use a tundish to collect the water.

Option 1: Through the left side panel



Option 2: Through the right side panel




#### 4.3 Connecting the refrigerant piping

See the outdoor unit installation manual for all guidelines, specifications and installation instructions.

# 4.3.1 To connect the refrigerant piping to the indoor unit

1 Connect the liquid stop valve from the outdoor unit to the refrigerant liquid connection of the indoor unit.



- a Refrigerant liquid connection
- b Refrigerant gas connection
- 2 Connect the gas stop valve from the outdoor unit to the refrigerant gas connection of the indoor unit.



#### **INFORMATION**

When the indoor unit is installed in a place with limited space, an optional pipe bend (EKHVTC) kit can be installed to facilitate the connection to the refrigerant gas and liquid connections of the indoor unit. For installation instructions, see the instruction sheet of the pipe bend kit.

#### 4.4 Connecting the water piping

#### 4.4.1 To connect the water piping




#### NOTICE

Do NOT use excessive force when connecting the piping. Deformation of the piping can cause malfunctioning of the

To facilitate service and maintenance, 2 shut-off valves and 1 overpressure bypass valve are provided. Mount the shut-off valves on the space heating water inlet and space heating water outlet. To ensure the minimum flow rate (and prevent overpressure), install the overpressure bypass valve on the space heating water outlet.

- Install the shut-off valves on the space heating water pipes.
- Screw the indoor unit nuts on the shut-off valve.
- Connect the domestic hot water in and out pipes to the indoor unit



- Space heating water out
- Space heating water in
- Domestic hot water out
- Domestic cold water in (cold water supply)



#### **NOTICE**

It is recommended to install shut-off valves to domestic cold water in and domestic hot water out connections. These shut-off valves are field supplied.



#### NOTICE



Overpressure bypass valve (delivered as accessory). We recommend to install the overpressure bypass valve in the space heating water circuit.

- Mind the minimum water volume when choosing the installation location of the overpressure bypass valve (at the indoor unit, or at the collector). See "3.2.1 To check the water volume and flow rate" on page 6.
- Mind the minimum flow rate when adjusting the overpressure bypass valve setting. See "3.2.1 To check the water volume and flow rate" on page 6 and "6.2.1 To check the minimum flow rate" on page 20.



#### **NOTICE**

Install air purge valves at all local high points.




#### NOTICE

A pressure relief valve (field supply) with an opening pressure of maximum 10 bar must be installed on the domestic cold water inlet connection in accordance with the applicable legislation.

#### 4.4.2 To connect the recirculation piping

Prerequisite: Only required if you need recirculation in your system.

- Remove the top panel from the unit, see "4.1.1 To open the indoor unit" on page 6.
- Cut out the rubber grommet on top of the unit, and remove the stop. The recirculation connector is placed below the hole.
- Route the recirculation piping through the grommet and connect it to the recirculation connector.



Reattach the top panel.

#### 4.4.3 To fill the water circuit

To fill the water circuit, use a field supply filling kit. Make sure you comply with the applicable legislation.



#### **INFORMATION**

Make sure both air purge valves (one on the magnetic filter, and one between the 3-way valve and flow sensor) are open.

#### To fill the domestic hot water tank 4.4.4

- Open every hot water tap in turn to purge air from the system pipe work.
- 2 Open the cold water supply valve.
- Close all water taps after all air is purged.
- Check for water leaks.
- Manually operate the field-installed pressure relief valve to ensure a free water flow through the discharge pipe.



#### NOTICE

To operate the system, the domestic hot water tank needs to be filled completely. Turning on the system when the tank is not full can damage the integrated anti-legionella heater and cause electrical errors.

#### 4.4.5 To insulate the water piping

The piping in the complete water circuit MUST be insulated to prevent condensation during defrost operation and reduction of the heating capacity.

If the temperature is higher than 30°C and the humidity is higher than RH 80%, the thickness of the insulation materials should be at least 20 mm to prevent condensation on the surface of the insulation.

#### 4.5 Connecting the electrical wiring

1

**DANGER: RISK OF ELECTROCUTION** 




**WARNING** 

ALWAYS use multicore cable for power supply cables.


# 4.5.1 To connect the electrical wiring on the indoor unit


- 1 To open the indoor unit, see "4.1.1 To open the indoor unit" on page 6 and "4.1.2 To open the switch box cover of the indoor unit" on page 7.
- 2 The wiring enters the unit from the top:



a, b, c Field wiring (see table below)

- d Factory-mounted cable for power supply of anti-legionella heater
- **3** Routing of the wiring inside the unit should be as follows. Fix the cable to the cable rail using cable ties:






Routing	Possible cables (depending on unit type and installed options)
а	Preferential power supply contact
Low voltage	User interface used as room thermostat (option)
	Power consumption digital inputs (field supply)
	Outdoor ambient temperature sensor (option)
	<ul> <li>Indoor ambient temperature sensor (option)</li> </ul>
	Electrical meters (field supply)
	Safety thermostat (field supply)
	Backup heater thermistor (backup heater option)
b	Interconnection cable
ligh voltage power	Normal kWh rate power supply
supply	Preferential kWh rate power supply
С	Heat pump convector (option)
High voltage control	Room thermostat (option)
signal	Shut-off valve (field supply)
	Domestic hot water pump (field supply)
	Alarm output
	Changeover to external heat source control
	Space heating operation control
	Backup heater thermal protector + backup heater connection (backup heater option)
d	Power supply for anti-legionella heater
High voltage power supply (factory-mounted cable)	

#### CAUTION

Do NOT push or place redundant cable length in the unit.


**4** Seal the low voltage wiring intake using the sealing tape (delivered as accessory).



#### 4.5.2 To connect the main power supply

1 Connect the main power supply.


In case of normal kWh rate power supply



Legend: see illustration below.

#### In case of preferential kWh rate power supply

Connect X11Y to X11YB.



- a Interconnection cable (=main power supply)
- **b** Normal kWh rate power supply
- c Preferential power supply contact
- 2 Fix the cables with cable ties to the cable tie mountings.



#### **INFORMATION**

In case of preferential kWh rate power supply, connect X11Y to X11YB. The necessity of separate normal kWh rate power supply to indoor unit (b) X2M/5+6 depends on the type of preferential kWh rate power supply.

Separate connection to the indoor unit is required:

- if preferential kWh rate power supply is interrupted when active, OR
- if no power consumption of the indoor unit is allowed at the preferential kWh rate power supply when active.



#### INFORMATION

The preferential kWh rate power supply contact is connected to the same terminals (X5M/9+10) as the safety thermostat. It is only possible for the system to have EITHER preferential kWh rate power supply OR a safety thermostat.


#### 4.5.3 To connect the shut-off valve

 Connect the valve control cable to the appropriate terminals as shown in the illustration below.



#### NOTICE

Wiring is different for a NC (normal closed) valve and a NO (normal open) valve.



2 Fix the cable with cable ties to the cable tie mountings.


#### 4.5.4 To connect the electrical meters



#### **INFORMATION**

In case of an electrical meter with transistor output, check the polarity. The positive polarity MUST be connected to X5M/6 and X5M/4; the negative polarity to X5M/5 and X5M/3.


1 Connect the electrical meters cable to the appropriate terminals as shown in the illustration below.



2 Fix the cable with cable ties to the cable tie mountings.

#### 4.5.5 To connect the domestic hot water pump


1 Connect the domestic hot water pump cable to the appropriate terminals as shown in the illustration below.



2 Fix the cable with cable ties to the cable tie mountings.

#### 4.5.6 To connect the alarm output


 Connect the alarm output cable to the appropriate terminals as shown in the illustration below.



- Installation of EKRP1HB is required.
- 2 Fix the cable with cable ties to the cable tie mountings.

# 4.5.7 To connect the space heating ON/OFF output


1 Connect the space heating ON/OFF output cable to the appropriate terminals as shown in the illustration below.



- a Installation of EKRP1HB is required.
- 2 Fix the cable with cable ties to the cable tie mountings.

# 4.5.8 To connect the changeover to external heat source


1 Connect the changeover to external heat source cable to the appropriate terminals as shown in the illustration below.



- a Installation of EKRP1HB is required.
- 2 Fix the cable with cable ties to the cable tie mountings.

# 4.5.9 To connect the power consumption digital inputs


1 Connect the power consumption digital inputs cable to the appropriate terminals as shown in the illustration below.



- a Installation of EKRP1AHTA is required.
- 2 Fix the cable with cable ties to the cable tie mountings.

# 4.5.10 To connect the safety thermostat (normal closed contact)

1 Connect the safety thermostat (normal closed) cable to the appropriate terminals as shown in the illustration below.



2 Fix the cable with cable ties to the cable tie mountings.



#### NOTICE

Make sure to select and install the safety thermostat according to the applicable legislation.

In any case, to prevent unnecessary tripping of the safety thermostat, it is recommended that ...

- ... the safety thermostat is automatically resettable.
- ... the safety thermostat has a maximum temperature variation rate of 2°C/min.
- ... there is a minimum distance of 2 m between the safety thermostat and the 3-way valve.



#### **INFORMATION**

After it is installed, do NOT forget to configure the safety thermostat. Without configuration, the indoor unit will ignore the safety thermostat contact.



#### **INFORMATION**

The preferential kWh rate power supply contact is connected to the same terminals (X5M/9+10) as the safety thermostat. It is only possible for the system to have EITHER preferential kWh rate power supply OR a safety thermostat.

#### 4.5.11 To connect the anti-legionella heater power supply



#### **WARNING**

The anti-legionella heater MUST have a dedicated power supply and MUST be protected by the safety devices required by the applicable legislation.




#### **CAUTION**

To guarantee the unit is completely earthed, always connect the anti-legionella heater power supply and the earth cable.


Make sure that the power supply is in accordance with the antilegionella heater capacity, as listed in the table below.

Anti-legionella heater capacity	Power supply	Maximum running current
2.4 kW	1N~ 230 V	11 A

Connect the anti-legionella heater power supply cable as follows:



- Factory-mounted cable connected to the anti-legionella heater contactor inside the lower switch box (K3M)
- Field wiring (see below)



F<sub>2</sub>B Overcurrent fuse (field supply). Recommended: 2-pole;

20 A; curve 400 V; tripping class C. Contactor (in the lower switch box)

K3M Q1DI Earth leakage circuit breaker (field supply)

SWB 2 Lower switch box

Terminal (field supply)

#### 4.6 Finishing the indoor unit installation

#### 4.6.1 To close the indoor unit

- Close the cover of the switch box.
- Put the switch box back into place. 2
- Reinstall the top panel. 3
- Reinstall the side panels.
- Reinstall the front panel.
- Reconnect the cables to the user interface panel.
- Reinstall the user interface panel.



#### NOTICE

When closing the indoor unit cover, make sure that the tightening torque does NOT exceed 4.1 N·m.

#### Configuration 5

#### 5.1 **Overview: Configuration**

This chapter describes what you have to do and know to configure the system after it is installed.



#### NOTICE

The explanation about the configuration in this chapter gives you ONLY basic explanations. For more detailed explanation and background information, see the installer reference quide.

If you do NOT configure the system correctly, it might NOT work as expected. The configuration influences the following:

- The calculations of the software
- · What you can see on and do with the user interface

#### How

You can configure the system via the user interface.

· First time - Configuration wizard. When you turn ON the user interface for the first time (via the indoor unit), the configuration wizard starts to help you configure the system.

#### **5 Configuration**

- Restart the configuration wizard. If the system is already configured, you can restart the configuration wizard. To restart the configuration wizard, go to Installer settings > Configuration wizard. To access Installer settings, see "5.1.1 To access the most used commands" on page 14.
- Afterwards. If necessary, you can make changes to the configuration in the menu structure or the overview settings.



#### **INFORMATION**

When the configuration wizard is finished, the user interface will show an overview screen and request to confirm. When confirmed, the system will restart and the home screen will be displayed.

#### Accessing settings - Legend for tables

You can access the installer settings using two different methods. However, NOT all settings are accessible via both methods. If so, the corresponding table columns in this chapter are set to N/A (not applicable).

Method	Column in tables
Accessing settings via the breadcrumb in the menu structure. To enable breadcrumbs, press the ? button in the home screen.	#
Accessing settings via the code in the <b>overview field settings</b> .	Code

#### See also:

- "To access the installer settings" on page 14
- "5.4 Menu structure: Overview installer settings" on page 19

#### 5.1.1 To access the most used commands

#### To change the user permission level

You can change the user permission level as follows:

1	Go to [B]: User profile.	<b>1</b> €○
2	Enter the applicable code for the user permission.	_
	Move the cursor from left to right.	<b>10</b> 0
	<ul> <li>Browse through the list of digits and change the selected digit.</li> </ul>	OØ
	Confirm the pincode and proceed.	<i>&amp;</i> ○

#### Installer pin code

The Installer pin code is **5678**. Additional menu items and installer settings are now available.



#### Advanced user pin code

The Advanced user pin code is **1234**. Additional menu items for the user are now visible.

#### User pin code

The User pin code is 0000.

#### To access the installer settings

- 1 Set the user permission level to Installer.
- 2 Go to [9]: Installer settings.

#### To modify an overview setting

Example: Modify [1-01] from 15 to 20.

All settings can be done using the menu structure. If for any reason it is required to change a setting using the overview settings, then the overview settings can be accessed as follows:

1	Set the u	_					
2	Go to [9. settings.	l]: Instal	ler sett	ings > O	verview field	(M:···)	
3		Turn the left dial to select the first part of the setting and confirm by pressing the dial.					
	0 1 2 3	00 01 02 03 04	05 06 07 08 09	OA OB OC OD OE			
4	Turn the setting	left dial	to sele	ct the se	econd part of the	€○	
	)1	00 01 <b>15</b> 02 03 04	05 06 07 08 09	OA OB OC OD OE			
5	Turn the	right dia	l to mo	odify the	value from 15 to 20.	○…◎	
	)1	00 01 <b>20</b> 02 03 04	05 06 07 08 09	0A 0B 0C 0D 0E			
6	Press the	e left dia	I to cor	nfirm the	new setting.	<b>@</b> *○	
7	Press the screen.	e center	button	to go ba	ack to the home	<b>^</b>	



#### INFORMATION

When you change the overview settings and you go back to the home screen, the user interface will show a popup screen and request to restart the system.

When confirmed, the system will restart and recent changes will be applied.

#### 5.2 Configuration wizard

After first power ON of the system, the user interface will guide you using the configuration wizard. This way you can set the most important initial settings. This way the unit will be able to run properly. Afterwards, more detailed settings can be done via the menu structure if required.

#### 5.2.1 Configuration wizard: Language

#	Code	Description
[7.1]	N/A	Language

#### 5.2.2 Configuration wizard: Time and date

#	Code	Description
[7.2]	N/A	Set the local time and date



#### **INFORMATION**

By default, daylight savings time is enabled and clock format is set to 24 hours. If you want to change these settings, you can do this in the menu structure (User settings > Time/date) once the unit is initialised.

#### 5.2.3 Configuration wizard: System

#### Indoor unit type

The indoor unit type is displayed, but cannot be adjusted.

#### Backup heater type

The backup heater is adapted to be connected to most common European electricity grids. The type of backup heater must be set on the user interface. For units with a built-in backup heater, the type of heater can be viewed but not changed.

#	Code	Description
[9.3.1]	[E-03]	0: No heater
		1: External heater

#### Domestic hot water

The following setting determines if the system can prepare domestic hot water or not, and which tank is used. This setting is read only.

#	Code	Description
[9.2.1]	[E-05] <sup>(*)</sup> [E-06] <sup>(*)</sup> [E-07] <sup>(*)</sup>	Integrated     The anti-legionella heater will also be used during disinfection.

(\*) Menu structure setting [9.2.1] replaces the following 3 overview settings:

[E-05] Can the system prepare domestic hot water? [E-06] Is a domestic hot water tank installed in the system?

[E-07] Is a domestic not water tank installed in the system [E-07] What kind of domestic hot water tank is installed?

#### **Emergency**

When the heat pump fails to operate, the optional backup heater and anti-legionella heater can serve as an emergency heater and either automatically or non-automatically take over the heat load.

- When auto emergency is set to Automatic and a heat pump failure occurs, the optional backup heater will automatically take over the heat load, and the anti-legionella heater will automatically take over the domestic hot water production.
- When auto emergency is set to Manual and a heat pump failure occurs, the domestic hot water and space heating operation will stop and need to be recovered manually via the user interface. To recover operation manually, go to the Malfunctioning main menu screen, where the user interface will then ask you to confirm whether the optional backup heater or anti-legionella heater can take over the heat load or not.

We recommend to set Emergency to Automatic if the house is unattended for longer periods.

#	Code	Description
[9.5]	N/A	0: Manual
		1: Automatic



#### **INFORMATION**

The auto emergency setting can be set in the menu structure of the user interface only.



#### **INFORMATION**

If [4-03]=1 or 3, then Emergency=Manual is not applicable for the anti-legionella heater.



#### INFORMATION

If a heat pump failure occurs and Emergency is set to Manual, the room frost protection function, the underfloor heating screed dryout function, and the water pipe antifreeze function will remain active even if the user does NOT confirm emergency operation.

#### Number of zones

The system can supply leaving water to up to 2 water temperature zones. During configuration, the number of water zones must be set.

#	Code	Description
[4.4]	[7-02]	0: Single zone     Only one leaving water temperature zone:
		• • • • • • • • • • • • • • • • • • •
		a: Main LWT zone
[4.4]	[7-02]	1: Dual zone     Two leaving water temperature zones.     The main leaving water temperature zone consists of the higher load heat emitters and a mixing station to achieve the desired leaving water temperature. In heating:
		<ul> <li>a: Additional LWT zone: Highest temperature</li> <li>b: Main LWT zone: Lowest temperature</li> </ul>



#### CAUTION

If there are 2 zones, it is important that the zone with the lowest water temperature is configured as the main zone, and the zone with the highest water temperature is configured as the additional zone. Not configuring the system in this way could cause damage to the heat emitters.



#### CAUTION

If there are 2 zones and the emitter types are wrongly configured, water of high temperature can be sent towards a low temperature emitter (underfloor heating). To avoid this:

- Install an aquastat/thermostatic valve to avoid too high temperatures towards a low temperature emitter.
- Make sure you set the emitter types for the main zone [2.7] and for the additional zone [3.7] correctly in accordance with the connected emitter.

#### 5.2.4 Configuration wizard: Backup heater

The backup heater is adapted to be connected to most common European electricity grids. If the backup heater is available, the voltage, configuration and capacity must be set on the user interface.

The capacities for the different steps of the backup heater must be set for the energy metering and/or power consumption control feature to work properly. When measuring the resistance value of each heater, you can set the exact heater capacity and this will lead to more accurate energy data.

#### Voltage

The optional external BUH can be set to 230V, 1ph, 230V, 3ph or 400V, 3ph.

#	Code	Description
[9.3.2]	[5-0D]	- 0: 230V, 1ph
		- 1: 230V, 3ph
		• 2: 400V, 3ph

#### Configuration

The backup heater can be configured in different ways. It can be chosen to have a 1-step only backup heater or a backup heater with 2 steps. If 2 steps, the capacity of the second step depends on this setting. It can also be chosen to have a higher capacity of the second step in emergency.

#	Code	Description
[9.3.3]	[4-0A]	• 0: Relay 1
		■ 1: Relay 1 / Relay 1+2 <sup>(a)</sup>
		• 2: Relay 1 / Relay 2 <sup>(a)</sup>
		<ul> <li>3: Relay 1 / Relay 2 Emergency Relay 1+2<sup>(a)</sup></li> </ul>

(a) Not available for 3V models.



#### INFORMATION

Settings [9.3.3] and [9.3.5] are linked. Changing one setting influences the other. If you change one, check if the other is still as expected.



#### INFORMATION

During normal operation, the capacity of the second step of the backup heater at nominal voltage is equal to [6-03]+[6-04].



#### **INFORMATION**

If [4-0A]=3 and emergency mode is active, the power usage of the backup heater is maximal and equal to  $2\times[6-03]+[6-04]$ .



#### **INFORMATION**

Only for systems with integrated domestic hot water tank: If the storage temperature set point is higher than 50°C, Daikin recommends NOT to disable the backup heater second step because it will have a big impact on the required time for the unit to heat up the domestic hot water tank.

#### Capacity step 1

#	Code	Description
[9.3.4]	[6-03]	- The capacity of the first step of the
		backup heater at nominal voltage.

#### Additional capacity step 2

#	Code	Description
[9.3.5]	[6-04]	<ul> <li>The capacity difference between the second and first step of the backup heater at nominal voltage. Nominal value depends on backup heater configuration.</li> </ul>

#### 5.2.5 Configuration wizard: Main zone

The most important settings for the main leaving water zone can be set here.

#### **Emitter type**

Depending on the system water volume and the heater emitter type of the main zone, the heat up of the main zone can take longer. This setting can compensate for a slow or a quick heating system during the heat up cycle. The target delta T for the main zone will depend on this setting.

In room thermostat control, this setting will influence the maximum modulation of the desired leaving water temperature.

Therefore it is important to set this correctly and in accordance with your system layout.

#	Code	Description
[2.7]	[2-0C]	0: Underfloor heating
		1: Fancoil unit
		2: Radiator

The setting of the emitter type has an influence on the space heating setpoint range and the target delta T in heating as follows:

Description	Space heating setpoint range	Target delta T in heating
0: Underfloor heating	Maximum 55°C	Variable
1: Fancoil unit	Maximum 55°C	Variable
2: Radiator	Maximum 65°C	Fixed 10°C



#### NOTICE

For radiators, the average emitter temperature will be lower compared to underfloor heating, due to the fixed delta T of 10°C. To compensate, you can:

- Increase the weather dependent curve desired temperatures [2.5].
- Enable leaving water temperature modulation and increase the maximum modulation [2.C].

#### Control

For the control of the unit there are 3 possibilities:

Control	In this control
Leaving water	Unit operation is decided based on the leaving water temperature regardless the actual room temperature and/or heating demand of the room.
External room thermostat	Unit operation is decided by the external thermostat or equivalent (e.g. heat pump convector).
Room thermostat	Unit operation is decided based on the ambient temperature of the user interface used as a room thermostat.

#	Code	Description
[2.9]	[C-07]	0: Leaving water
		1: External room thermostat
		2: Room thermostat

#### Setpoint mode

In Fixed mode, the desired leaving water temperature does NOT depend on the outdoor ambient temperature.

In Weather dependent mode, the desired leaving water temperature depends on the outdoor ambient temperature.

#	Code	Description
[2.4]	N/A	Setpoint mode
		0: Fixed
		2: Weather dependent

When weather dependent operation is active, low outdoor temperatures will result in warmer water and vice versa. During weather dependent operation, the user has the possibility to shift the water temperature up or down by a maximum of  $10^{\circ}$ C.

#### Schedule

Indicates if the desired leaving water temperature is according to a schedule. Influence of the LWT setpoint mode [2.4] is as follows:

- In Fixed LWT setpoint mode, the scheduled actions consist of desired leaving water temperatures, either preset or custom.
- In Weather dependent LWT setpoint mode, the scheduled actions consist of desired shift actions, either preset or custom.

#	Code	Description
[2.1]	N/A	• 0: No
		• 1: Yes

#### 5.2.6 Configuration wizard: Additional zone

The most important settings for the additional leaving water zone can be set here.

#### **Emitter type**

For more info about this functionality, see "5.2.5 Configuration wizard: Main zone" on page 16.

#	Code	Description
[3.7]	[2-0D]	0: Underfloor heating
		1: Fancoil unit
		2: Radiator

#### Control

The control type is displayed here, but cannot be adjusted. It is determined by the control type of the main zone. For more info about the functionality, see "5.2.5 Configuration wizard: Main zone" on page 16.

#	Code	Description
[3.9]	N/A	0: Leaving water if the control type of the main zone is Leaving water.
		<ul> <li>1: External room thermostat if the control type of the main zone is External room thermostat or Room thermostat.</li> </ul>

#### Setpoint mode

For more info about this functionality, see "5.2.5 Configuration wizard: Main zone" on page 16.

#	Code	Description
[3.4]	N/A	0: Fixed
		2: Weather dependent

If you choose Weather dependent, the next screen will be the detailed screen with weather-dependent curves. Also see "5.2.7 Detailed screen with weather-dependent curve" on page 17.

#### Setpoint mode

For more info about this functionality, see "5.2.5 Configuration wizard: Main zone" on page 16.

#	Code	Description
[3.4]	N/A	0: Fixed
		1: WD heating, fixed cooling
		2: Weather dependent

If you choose Weather dependent, the next screen will be the detailed screen with weather-dependent curves. Also see "5.2.7 Detailed screen with weather-dependent curve" on page 17.

#### Schedule

Indicates if the desired leaving water temperature is according to a schedule. Also see "5.2.5 Configuration wizard: Main zone" on page 16.

	#	Code		Description
[	3.1]	N/A	•	0: No
				1: Yes


### 5.2.7 Detailed screen with weather-dependent

When weather dependent operation is active the desired tank temperature is determined automatically depending on the averaged outdoor temperature. When the outdoor temperature is lower the tank temperature will need to be higher as the water pipes will be colder and vice versa.

The weather-dependent curves are defined by two setpoints:

- Setpoint (X1, Y2)
- Setpoint (X2, Y1)

Weather-dependent curve:



Possible actions on this screen		
100	Go through the temperatures.	
001	Change the temperature.	
OQm	Go to the next temperature.	
@:···	Confirm changes and proceed.	

Item	Description	
а	Possible weather dependent zones:	
	Main zone or additional zone heating	
	■ ☐::: Domestic hot water	
X, X1, X2	Outdoor ambient temperature	
Y, Y1, Y2	Desired tank temperature or leaving water temperature. The symbol shown here corresponds to the heat emitter for that zone:  Underfloor heating Fan coil unit  Radiator  Domestic hot water tank	

#### 5.2.8 Configuration wizard: Tank

#### Heat up mode

The domestic hot water can be prepared in 3 different ways. They differ from each other by the way the desired tank temperature is set and how the unit acts upon it.

#	Code	Description
[5.6]	[6-0D]	Heat up mode
		0: Reheat only: Only reheat operation is allowed.
		<ul> <li>1: Schedule + reheat: The domestic hot water tank is heated according to a schedule and between the scheduled heat up cycles, reheat operation is allowed.</li> </ul>
		<ul> <li>2: Schedule only: The domestic hot water tank can ONLY be heated according to a schedule.</li> </ul>

See the operation manual for more details.

#### Comfort setpoint

Only applicable when domestic hot water preparation is Schedule only or Schedule + reheat. When programming the schedule, you can make use of the comfort setpoint as a preset value. When you later want to change the storage setpoint, you only have to do it in one place.

The tank will heat up until the **storage comfort temperature** has been reached. It is the higher desired temperature when a storage comfort action is scheduled.

Additionally, a storage stop can be programmed. This feature puts a stop to tank heating even if the setpoint has NOT been reached. Only program a storage stop when tank heating is absolutely undesirable.

#	Code	Description
[5.2]	[6-0A]	Comfort setpoint
		• 30°C~[6-0E]°C

#### Eco setpoint

The **storage economic temperature** denotes the lower desired tank temperature. It is the desired temperature when a storage economic action is scheduled (preferably during day).

#	Code	Description
[5.3]	[6-0B]	Eco setpoint
		■ 30°C~min(50,[6-0E])°C

#### Reheat setpoint

#### Desired reheat tank temperature, used:

- in Schedule + reheat mode, during reheat mode: the guaranteed minimum tank temperature is set by the Reheat setpoint minus the reheat hysteresis. If the tank temperature drops below this value, the tank is heated up.
- during storage comfort, to prioritize the domestic hot water preparation. When the tank temperature rises above this value, domestic hot water preparation and space heating/cooling are executed sequentially.

#	Code	Description
[5.4]	[6-0C]	Reheat setpoint
		• 30°C~min(50,[6-0E])°C

#### 5.3 Settings menu

You can set additional settings using the main menu screen and its submenus. The most important settings are presented here.

#### 5.3.1 Main zone

#### Thermostat type

Only applicable in external room thermostat control.



#### NOTICE

If an external room thermostat is used, the external room thermostat will control the room frost protection. However, the room frost protection is only possible if the leaving water temperature control on the unit's user interface is turned ON.

#	Code	Description
[2.A]	[C-05]	External room thermostat type for the main zone:
		<ul> <li>1: 1 contact: The used external room thermostat can only send a thermo ON/OFF condition. There is no separation between heating or cooling demand.</li> </ul>
		<ul> <li>2: 2 contacts: The used external room thermostat can send a separate heating/cooling thermo ON/OFF condition.</li> </ul>

#### 5.3.2 Additional zone

#### Thermostat type

Only applicable in external room thermostat control. For more info about the functionality, see "5.3.1 Main zone" on page 18.

#	Code	Description
[3.A]	[C-06]	External room thermostat type for the additional zone:
		1: 1 contact
		2: 2 contacts


#### 5.3.3 Information

#### Dealer information

The installer can fill in his contact number here.

# Code		Code Description	
[8.3]	N/A	Number that users can call in case of	
		problems.	

#### 5.4 Menu structure: Overview installer settings





#### **INFORMATION**

Solar kit settings are shown but are NOT applicable for this unit. Settings shall NOT be used or changed.



#### **INFORMATION**

Depending on the selected installer settings and unit type, settings will be visible/invisible.



#### **INFORMATION**

**Anti-legionella heater.** In the menu structure the term "Booster heater" is used. However, this is actually an anti-legionella heater.

#### 6 Commissioning



#### NOTICE

NEVER operate the unit without thermistors and/or pressure sensors/switches. Burning of the compressor might result.



#### **INFORMATION**

The software is equipped with an "installer-on-site" mode ([9.G]: Disable protections), that disables automatic operation by the unit. At first installation, setting Disable protections is by default set to Yes, meaning automatic operation is disabled. All protective functions are then disabled. If the user interface home pages are off, the unit will NOT operate automatically. To enable automatic operation and the protective functions, set Disable protections to No.

36 hours after the first power-on, the unit will automatically set Disable protections to No, ending "installer-on-site" mode and enabling the protective functions. If – after first installation – the installer returns to the site, the installer has to set Disable protections to Yes manually.

#### 6.1 Checklist before commissioning

After the installation of the unit, first check the following items. Once all below checks are fulfilled, the unit MUST be closed, ONLY then can the unit be powered up.

	You read the complete installation instructions, as described in the <b>installer reference guide</b> .
	The indoor unit is properly mounted.
П	Only if you use the optional backup heater:
	The backup heater is properly mounted.
	The <b>outdoor unit</b> is properly mounted.
	The following <b>field wiring</b> has been carried out according to this document and the applicable legislation:
	Between the local supply panel and the outdoor unit
	Between indoor unit and outdoor unit
	Between the local supply panel and the indoor unit
	Between the indoor unit and the valves (if applicable)
	Between the indoor unit and the room thermostat (if applicable)
	The system is properly <b>earthed</b> and the earth terminals are tightened.
	The <b>fuses</b> or locally installed protection devices are installed according to this document, and have NOT been bypassed.
	The <b>power supply voltage</b> matches the voltage on the identification label of the unit.
	There are NO <b>loose connections</b> or damaged electrical components in the switch box.
	There are NO damaged components or squeezed pipes on the inside of the indoor and outdoor units.
	Only if you use the optional backup heater:
	Depending on the backup heater type, <b>backup heater circuit breaker</b> F1B (on the switch box of the backup heater) is turned ON.
	The anti-legionella heater circuit breaker F2B (field supply) is turned ON.
	There are NO refrigerant leaks.

The <b>refrigerant pipes</b> (gas and liquid) are thermally insulated.
The correct pipe size is installed and the <b>pipes</b> are properly insulated.
There is NO water leak inside the indoor unit.
The <b>shut-off valves</b> are properly installed and fully open.
The <b>stop valves</b> (gas and liquid) on the outdoor unit are fully open.
The air purge valve is open (at least 2 turns).
The <b>pressure relief valve</b> purges water when opened.
The <b>minimum water volume</b> is guaranteed in all conditions. See "To check the water volume" in "3.2 Preparing water piping" on page 6.
The domestic hot water tank is filled completely.

#### 6.2 Checklist during commissioning

#### 6.2.1 To check the minimum flow rate

Confirm according to the hydraulic configuration which space heating loops can be closed due to mechanical, electronic, or other valves.	_
Close all space heating loops that can be closed (see previous step).	_
Start the pump test run operation (see "6.2.4 To perform an actuator test run" on page 21).	_
During pump test run operation, go to Sensors.	<b>(</b> €○
Select the flow rate information. During test run operation, the unit can operate below the minimum required flow rate.	<b>(</b> R****)
Modify the bypass valve setting to reach the minimum required flow rate + 2 l/min.	_
	which space heating loops can be closed due to mechanical, electronic, or other valves.  Close all space heating loops that can be closed (see previous step).  Start the pump test run operation (see "6.2.4 To perform an actuator test run" on page 21).  During pump test run operation, go to Sensors.  Select the flow rate information. During test run operation, the unit can operate below the minimum required flow rate.  Modify the bypass valve setting to reach the

Minimum required flow rate
12 l/min

#### 6.2.2 To perform an air purge

**Conditions:** Make sure all operation is disabled. Go to the Operation menu and turn off Room, Space heating/cooling and Tank operation.

1	Set the user permission level to Installer. See "To change the user permission level" on page 14.	_
2	Go to [A.3]: Commissioning > Air purge.	<b>1</b> €○
3	Select OK to confirm.	<b>1</b> €○
	<b>Result:</b> The air purge starts. It stops automatically when air purge cycle is finished.	
	To stop the air purge manually:	_
	1 Go to Stop air purge.	<b>1</b> €○
	2 Select OK to confirm.	O@

#### Air purging heat emitters or collectors

We recommend to purge air with the unit's air purge function (see above). However, if you purge air from the heat emitters or collectors, mind the following:



#### **WARNING**

Air purging heat emitters or collectors. Before you purge air from heat emitters or collectors, check if  $\bigcirc$  or  $\bigcirc$  is displayed on the home screen of the user interface.

- If not, you can purge air immediately.
- If yes, make sure that the room where you want to purge air is sufficiently ventilated. Reason: Refrigerant might leak into the water circuit, and subsequently into the room when you purge air from the heat emitters or collectors.

#### 6.2.3 To perform an operation test run

**Conditions:** Make sure all operation is disabled. Go to the Operation menu and turn off Room, Space heating/cooling and Tank operation.

1	Set the user permission level to Installer. See "To change the user permission level" on page 14.	_
2	Go to [A.1]: Commissioning > Operation test run.	<b>1</b> €○
3	Select a test from the list. <b>Example:</b> Heating.	<b>1</b> €○
4	Select OK to confirm.	<b>€</b> 00000
	<b>Result:</b> The test run starts. It stops automatically when done (±30 min).	
	To stop the test run manually:	_
	1 Go to Stop test run.	<b>1</b> €○
	2 Select OK to confirm.	<b>€</b> ○



#### **INFORMATION**

When starting up the system in a cold climate, and NO backup heater kit was installed, it may be required to start up with a small water volume. To do this, gradually open the heat emitters. As a result, the water temperature will gradually rise. Monitor the inlet water temperature ([6.1.6] in the menu structure) and make sure it does NOT drop below 15°C.

If the installation of the unit has been done correctly, the unit will start up during test operation in the selected operation mode. During test mode, the correct operation of the unit can be checked by monitoring its leaving water temperature (heating/cooling mode) and tank temperature (domestic hot water mode).

To monitor the temperature:

1	Go to Sensors.	<b>1</b> €○	
2	Select the temperature information.	<b>1</b> 04○	

#### 6.2.4 To perform an actuator test run

**Conditions:** Make sure all operation is disabled. Go to the Operation menu and turn off Room, Space heating/cooling and Tank operation.

Purpose of the actuator test run is to confirm the operation of the different actuators (e.g., when you select Pump, a test run of the pump will start).

1	Set the user permission level to Installer. See "To change the user permission level" on page 14.	_
2	Go to [A.2]: Commissioning > Actuator test run.	<b>€</b> 0○
3	Select a test from the list. <b>Example:</b> Pump.	<b>1</b> €○

4	Se	elect OK to confirm.	<b>™</b> ○
		esult: The actuator test run starts. It stops tomatically when done (±30 min).	
	To stop the test run manually:		_
	1	Go to Stop test run.	<b>1</b> €○
	2	Select OK to confirm.	<b>1</b> 00+○

#### Possible actuator test runs

- Booster heater test
- Backup heater 1 test (if applicable)
- Backup heater 2 test (if applicable)
- Pump test



#### **INFORMATION**

Make sure that all air is purged before executing the test run. Also avoid disturbances in the water circuit during the test run.

- Shut off valve test
- Diverter valve test
- Bivalent signal test
- · Alarm output test
- C/H signal test
- DHW pump test

# 6.2.5 To perform an underfloor heating screed dryout

**Conditions:** Make sure all operation is disabled. Go to the Operation menu and turn off Room, Space heating/cooling and Tank operation.

1	Set the user permission level to Installer. See "To change the user permission level" on page 14.	_				
2	Go to [A.4]: Commissioning > UFH screed dryout.					
3	Set a dryout program: go to Program and use the UFH screed dryout programming screen.					
4	4 Select OK to confirm.					
	<b>Result:</b> The underfloor heating screed dryout starts. It stops automatically when done.					
	To stop the test run manually:					
	1 Go to Stop UFH screed dryout.					
	2 Select OK to confirm.					



#### NOTICE

To perform an underfloor heating screed dryout, room frost protection needs to be disabled ([2-06]=0). By default, it is enabled ([2-06]=1). However, due to the "installer-on-site" mode (see "Commissioning"), room frost protection will be automatically disabled for 36 hours after the first power-on.

If the screed dryout still needs to be performed after the first 36 hours of power-on, manually disable room frost protection by setting [2-06] to "0", and KEEP it disabled until the screed dryout has finished. Ignoring this notice will result in cracking of the screed.

#### 7 Hand-over to the user



#### NOTICE

For the underfloor heating screed dryout to be able to start, make sure the following settings are met:

- **•** [4-00]=1
- [C-02]=0
- [D-01]=0
- **•** [4-08]=0
- [4-01]≠1

#### 7 Hand-over to the user


Once the test run is finished and the unit operates properly, please make sure the following is clear for the user:

- Fill in the installer setting table (in the operation manual) with the actual settings.
- Make sure that the user has the printed documentation and ask him/her to keep it for future reference. Inform the user that he can find the complete documentation at the URL mentioned earlier in this manual.
- Explain the user how to properly operate the system and what to do in case of problems.
- Show the user what to do for the maintenance of the unit.
- Explain the user about energy saving tips as described in the operation manual.

#### 8 **Technical data**

A subset of the latest technical data is available on the regional Daikin website (publicly accessible). The full set of latest technical data is available on the Daikin Business Portal (authentication required).

#### 8.1 Piping diagram: Indoor unit



DAIKIN

- Water side
- Refrigerant side
- Field installed
- a1 Space heating water IN
- Space heating water OUT
  Domestic hot water: cold water IN
- Domestic hot water: hot water OUT
- Gas refrigerant IN (heating mode; condenser)
- Liquid refrigerant OUT (heating mode; condenser)
- Liquid refrigerant IN (cooling mode; evaporator)
- Gas refrigerant OUT (cooling mode; evaporator)
  Plate heat exchanger
  Shut-off valve for service (if equipped)
- Expansion vessel
- Magnetic filter/dirt separator
- Safety valve
- Air purge
- Drain valve
- Pump
- Flow sensor

B1PW Space heating water pressure sensor B2PR

Refrigerant pressure sensor

M3S 3-way valve (space heating/domestic hot water) R1T Thermistor (heat exchanger – water OUT)

Thermistor (liquid refrigerant)
Thermistor (heat exchanger – water IN) R3T

R4T **R5T, R8T** Thermistor (tank)

Screw connection Flare connection

Quick coupling

Brazed connection

#### 8.2 Wiring diagram: Indoor unit

See the internal wiring diagram supplied with the unit (on the inside of the indoor unit switch box cover). The abbreviations used are listed below.

#### Notes to go through before starting the unit

English	Translation
Notes to go through before	Notes to go through before
starting the unit	starting the unit
X1M	Main terminal
X2M	Field wiring terminal for AC
X3M	Backup heater terminal
X5M	Field wiring terminal for DC
X8M	Anti-legionella heater power supply terminal
	Earth wiring
	Field supply
1	Several wiring possibilities
	Option
	Not mounted in switch box
	Wiring depending on model
	PCB
Note 1: Connection point of the power supply for the anti- legionella heater should be foreseen outside the unit.	Note 1: Connection point of the power supply for the antilegionella heater should be foreseen outside the unit.
Optional backup heater power supply	Optional backup heater power supply
□ 1N~, 230 V, 6 kW	□ 1N~, 230 V, 6 kW
□ 3N~, 400 V, 6 kW	□ 3N~, 400 V, 6 kW
User installed options	User installed options
□ LAN adapter	□ LAN adapter
☐ Backup heater	☐ Backup heater
☐ Remote user interface	☐ User interface used as room thermostat
☐ Ext. indoor thermistor	☐ External indoor thermistor
☐ Ext outdoor thermistor	☐ External outdoor thermistor
☐ Digital I/O PCB	☐ Digital I/O PCB
☐ Demand PCB	☐ Demand PCB
Main LWT	Main leaving water temperature
☐ On/OFF thermostat (wired)	☐ On/OFF thermostat (wired)
☐ On/OFF thermostat (wireless)	☐ On/OFF thermostat (wireless)
☐ Ext. thermistor	☐ External thermistor
☐ Heat pump convector	☐ Heat pump convector
Add LWT	Additional leaving water temperature
☐ On/OFF thermostat (wired)	☐ On/OFF thermostat (wired)
☐ On/OFF thermostat (wireless)	☐ On/OFF thermostat (wireless)
☐ Ext. thermistor	☐ External thermistor
☐ Heat pump convector	☐ Heat pump convector

#### Position in switch box

English	Translation
Position in switch box	Position in switch box

#### Legend

A1P		Main PCB
A2P	*	On/OFF thermostat (PC=power circuit)

A3P	*	Heat pump convector	
A4P	*	Digital I/O PCB	
A8P	*	Demand PCB	
A9P		Status indicator	
A10P		MMI (= user interface connected to the indoor unit) – Power supply unit PCB	
A11P		MMI (= user interface connected to the indoor unit) – Main PCB	
A12P		MMI display PCB	
A13P	*	LAN adapter	
A14P	*	User interface used as room thermostat – PCB	
A15P	*	Receiver PCB (wireless On/OFF thermostat)	
B1L		Flow sensor	
B1PR		Refrigerant pressure sensor	
B1PW		Water pressure sensor	
CN* (A4P)	*	Connector	
DS1(A8P)	*	DIP switch	
F2B	#	Overcurrent fuse anti-legionella heater	
F2T	"	Thermal fuse anti-legionella heater	
F1U, F2U (A4P)	*	Fuse 5 A 250 V for digital I/O PCB	
FU1 (A1P)		Fuse T 5 A 250 V for PCB	
FU2 (A10P)		Fuse T 1.6 A 250 V for PCB	
K3M			
		Contactor anti-legionella heater	
K*R (A4P)		Relay on PCB	
M1P		Main supply pump	
M2P	#	Domestic hot water pump	
M2S	#	2-way valve for cooling mode	
M3S		3-way valve for floorheating/domestic hot water	
P1M		MMI display	
PC (A15P)	*	Power circuit	
PHC1 (A4P)	*	Optocoupler input circuit	
Q2L		Thermal protector anti-legionella heater	
Q4L	#	Safety thermostat	
Q*DI	#	Earth leakage circuit breaker	
R1H (A2P)	*	Humidity sensor	
R1T (A1P )		Outlet water heat exchanger thermistor	
R1T (A2P)	*	Ambient sensor On/OFF thermostat	
R1T (A14P)	*	Ambient sensor user interface	
R2T (A2P)	*	External sensor (floor or ambient)	
R3T		Refrigerant liquid side thermistor	
R4T		Inlet water thermistor	
R5T, R8T		Domestic hot water thermistor	
R6T	*	External indoor or outdoor ambient thermistor	
S1S	#	Preferential kWh rate power supply contact	
S1S S2S	#	Preferential kWh rate power supply contact Electrical meter pulse input 1	
S2S		Electrical meter pulse input 1	
S2S S3S	#	Electrical meter pulse input 1 Electrical meter pulse input 2	
\$2\$ \$3\$ \$6\$~\$9\$	#	Electrical meter pulse input 1 Electrical meter pulse input 2 Digital power limitation inputs	
S2S S3S	# # *	Electrical meter pulse input 1 Electrical meter pulse input 2	

SW3~5 (A12P)		Push buttons
TR1		Power supply transformer
X8M	#	Anti-legionella heater power supply terminal strip
X*, X*A, X*Y, Y*		Connector
X*M		Terminal strip

<sup>\*</sup> Optional # Field supply

#### Translation of text on wiring diagram

English	Translation
(1) Main power connection	(1) Main power connection
For preferential kWh rate power supply	For preferential kWh rate power supply
Indoor unit supplied from outdoor	Indoor unit supplied from outdoor
Normal kWh rate power supply	Normal kWh rate power supply
Only for normal power supply (standard)	Only for normal power supply (standard)
Only for preferential kWh rate power supply (outdoor)	Only for preferential kWh rate power supply (outdoor)
Outdoor unit	Outdoor unit
Preferential kWh rate power supply contact: 16 V DC detection (voltage supplied by PCB)	Preferential kWh rate power supply contact: 16 V DC detection (voltage supplied by PCB)
SWB	Switch box
Use normal kWh rate power supply for indoor unit	Use normal kWh rate power supply for indoor unit
(3) User interface	(3) User interface
Only for LAN adapter	Only for the LAN adapter
Only for remote user interface EKRUDAS	Only for the user interface used as room thermostat (EKRUDAS)
(4) Domestic hot water tank	(4) Domestic hot water tank
Anti-legionella heater power	
supply	Anti-legionella heater power supply
supply	supply
supply SWB	supply Switch box
supply SWB (5) Ext. thermistor	supply Switch box (5) External thermistor
supply SWB (5) Ext. thermistor SWB	supply Switch box (5) External thermistor Switch box
supply SWB (5) Ext. thermistor SWB (6) Field supplied options 12 V DC pulse detection (voltage	supply Switch box (5) External thermistor Switch box (6) Field supplied options 12 V DC pulse detection (voltage
supply SWB (5) Ext. thermistor SWB (6) Field supplied options 12 V DC pulse detection (voltage supplied by PCB)	supply Switch box (5) External thermistor Switch box (6) Field supplied options 12 V DC pulse detection (voltage supplied by PCB)
supply SWB (5) Ext. thermistor SWB (6) Field supplied options 12 V DC pulse detection (voltage supplied by PCB) 230 V AC supplied by PCB	supply Switch box (5) External thermistor Switch box (6) Field supplied options 12 V DC pulse detection (voltage supplied by PCB) 230 V AC supplied by PCB

English	Translation
Electrical meters	Electrical meters
For safety thermostat	For safety thermostat
Inrush	Inrush current
Max. load	Maximum load
Normally closed	Normally closed
Normally open	Normally open
Safety thermostat contact: 16 V DC detection (voltage supplied by PCB)	Safety thermostat contact: 16 V DC detection (voltage supplied by PCB)
Shut-off valve	Shut-off valve
SWB	Switch box
(7) Optional BUH	(7) Optional backup heater
SWB	Switch box
(7) Option PCBs	(7) Option PCBs
Alarm output	Alarm output
Changeover to ext. heat source	Changeover to external heat source
Max. load	Maximum load
Min. load	Minimum load
Only for demand PCB option	Only for demand PCB option
Only for digital I/O PCB option	Only for digital I/O PCB option
Options: ext. heat source output, alarm output	Options: external heat source output, alarm output
Options: On/OFF output	Options: On/OFF output
Power limitation digital inputs: 12 V DC / 12 mA detection (voltage supplied by PCB)	Power limitation digital inputs: 12 V DC / 12 mA detection (voltage supplied by PCB)
Space C/H On/OFF output	Space cooling/heating On/OFF output
SWB	Switch box
(8) External On/OFF thermostats and heat pump convector	(8) External On/OFF thermostats and heat pump convector
Additional LWT zone	Additional leaving water temperature zone
Main LWT zone	Main leaving water temperature zone
Only for external sensor (floor/ambient)	Only for external sensor (floor or ambient)
Only for heat pump convector	Only for heat pump convector
Only for wired On/OFF thermostat	Only for wired On/OFF thermostat
Only for wireless On/OFF thermostat	Only for wireless On/OFF thermostat

#### Electrical connection diagram

For more details, please check the unit wiring. Standard part Power supply Outdoor unit Notes: Only for normal power supply installation unit power supply: 230 V + earth - In case of signal cable: keep minimum distance to power cables >5 cm X1M: L-N-earth ① Only for preferential kWh rate power supply installation
Unit preferential kWh rate power supply:
230 V + earth
3 core Normal kWh rate power supply for indoor unit: 230 V X1M: 1-2-3 Preferential kWh rate power supply contact Field supply Field supply Indoor unit Safety thermostat Q4L Only for \*KRP1HB\* X1M: 1-2-3 X2M: 5-6 A4P: Y1-YC X2M: 7-9 Alarm output X5M: 9-10 A4P: X1-X2 Changeover to ext. heat source output Power supply A4P: Y2-YC X2M: 7-9 Cooling/heating On/OFF output Anti-legionella heater power supply (2, 4 kW): 230 V + earth X8M: L-N-earth X2M: 1-2 Circulation pump for DHW 2-way valve Backup heater option NO valve: X2M: 21-28 NC valve: X2M: 21-29 M2S for cooling mod (FKLBUHCB6W1) X15M: 1-2 X5M: 1-2 X5M: 5-6 Electricity meter pulse input X15M: 8-9-10 X3M: 3-4-5 X5M: 3-4 X3M: 1-2 Only for KRCS01-1 or EKRSCA1 F1B: L1-L2-L3-N + PE X5M: 7-8 external thermistor (indoor or outdoor) or L-N + PE Power supply External room thermostat / Heat pump convector (main and/or additional zone) Backup heater power supply (6 kW): 400 V or 230 V + earth Optional part 3 Only for \*KRTW (wired room thermostat) 3 core for C/H operation 2 core for H only operation main: X2M: 30-34-35 add: X2M: 30-34a-35a signal /// A2P: X1M: C-com-H Field supply Only for \*KRTR (wireless room thermostat) Only for \*KRP1AHTA 3 Only for \*KRTETS 5 core for C/H operation 4 core for H only operation 2 core (3m included) A15P: X1M: H-C-com 4 A2P: X1M: 1-3 Power limitation signal /// demand input 1 Only for (heat pump convector) Power limitation 3 demand input 2 Power limitation demand input 3 A3P: X11M: 5-6 A8P: X801M: 3-5 signal A8P: X801M: 4-5 and input 4 signal Only for EKRUDAS A14P: P1-P2 user interface X5M: 11-12 A13P: P1-P2 LAN adapter 4D112068B

# 8.3 Table 1 – Maximum refrigerant charge allowed in a room: indoor unit

A <sub>room</sub> (m <sup>2</sup> )	Maximum refrigerant charge in a room (m <sub>max</sub> ) (kg)
	H=600 mm
1	0.138
2	0.276
3	0.414
4	0.553
5	0.691
6	0.829
7	0.907
8	0.970
9	1.028
10	1.084
11	1.137
12	1.187
13	1.236
14	1.283
15	1.328
16	1.371
17	1.413
18	1.454
19	1.494
20	1.533
21	1.571
22	1.608
23	1.644
24	1.679
25	1.714
26	1.748
27	1.781
28	1.814
29	1.846
30	1.877
31	1.909

#### H

#### **INFORMATION**

- For floorstanding models, the value of "Installation height (H)" is considered 600 mm to comply to IEC 60335-2-40:2013 A1 2016 Clause GG2.
- For intermediate A<sub>room</sub> values (i.e. when A<sub>room</sub> is between two values from the table), consider the value that corresponds to the lower A<sub>room</sub> value from the table. If A<sub>room</sub>=12.5 m², consider the value that corresponds to "A<sub>room</sub>=12 m²".

# 8.4 Table 2 – Minimum floor area: indoor unit

m <sub>c</sub> (kg)	Minimum floor area (m²)	
	H=600 mm	
1.84	28.81	
1.86	29.44	
1.88	30.08	
1.90	30.72	



#### **INFORMATION**

- For floorstanding models, the value of "Installation height (H)" is considered 600 mm to comply to IEC 60335-2-40:2013 A1 2016 Clause GG2.
- For intermediate m<sub>c</sub> values (i.e. when m<sub>c</sub> is between two values from the table), consider the value that corresponds to the higher m<sub>c</sub> value from the table. If m<sub>c</sub>=1.87 kg, consider the value that corresponds to "m<sub>c</sub>=1.88 kg".
- Systems with a total refrigerant charge (m<sub>c</sub>) <1.84 kg (i.e. if the piping length is <27 m) are NOT subjected to any requirements to the installation room.
- Charges >1.9 kg are NOT allowed in the unit.

# 8.5 Table 3 – Minimum venting opening area for natural ventilation: indoor unit

m <sub>c</sub>	m <sub>max</sub>	dm=m <sub>c</sub> -m <sub>max</sub> (kg)	Minimum venting opening area (cm²)
			H=600 mm
1.9	0.1	1.80	729
1.9	0.3	1.60	648
1.9	0.5	1.40	567
1.9	0.7	1.20	486
1.9	0.9	1.00	418
1.9	1.1	0.80	370
1.9	1.3	0.60	301
1.9	1.5	0.40	216
1.9	1.7	0.20	115



#### **INFORMATION**

- For floorstanding models, the value of "Installation height (H)" is considered 600 mm to comply to IEC 60335-2-40:2013 A1 2016 Clause GG2.
- For intermediate dm values (i.e. when dm is between two dm values from the table), consider the value that corresponds to the higher dm value from the table. If dm=1.55 kg, consider the value that corresponds to "dm=1.6 kg".

ERE

